

WPD West Midlands Appendix G

GSP	Part 1 [MW]	Part 2 [MW]	Part 3 [MW]	Part 4 [MW]	Part 5 [MW]	Thermal Materiality Headroom [MW] **	Capacity in Project Progression/ Modification Application [MW]	Total Aggregated Developer Capacity [MW]	Fault Level Headroom [kA]	Appendix G Approval Date
Bishops Wood*	80.8	304.5	0.0	0.0	0.0*	N/A	42.0	389.5	1.1	16/07/2020
Bushbury	52.7	51.9	0.0	0.0	74.3	N/A	N/A	178.9	2.8	16/07/2020
Bustleholm	8.9	56.2	0.0	0.0	50.8	N/A	N/A	115.9	1.4	16/07/2020
Cellarhead	135.5	63.1	0.0	0.0	152.7	N/A	N/A	351.2	5.2	16/07/2020
East Claydon*	12.3	13.1	0.0	0.0	50.0	N/A	N/A	75.3	0.0*	16/07/2020
Feckenham	123.8	397.8	0.0	0.0	50.0	N/A	N/A	571.6	2.0	07/05/2020
Iron Acton*	64.5	288.2	0.0	49.9	0.0*	N/A	49.9	441.2	1.6	16/07/2020
Ironbridge*	57.5	109.0	0.0	0.0	0.0*	N/A	15.0	170.2	2.3	16/07/2020
Kitwell	12.5	8.0	0.0	0.0	52.0	N/A	N/A	72.5	2.9	16/07/2020
Lea Marston	22.1	16.1	0.0	0.0	54.3	N/A	N/A	92.5	2.9	16/07/2020
Nechells East	176.0	50.0	0.0	0.0	96.7	N/A	N/A	322.7	4.4	16/07/2020
Ocker Hill	4.0	63.2	0.0	0.0	90.0	N/A	N/A	157.2	1.4	16/07/2020
Oldbury	38.5	57.9	0.0	0.0	12.1	N/A	N/A	108.5	1.7	16/07/2020
Penn	15.9	64.0	0.0	0.0	173.8	N/A	N/A	253.7	3.9	16/07/2020
Port Ham	33.8	424.0	21.8	5.0	132.8	0.0	N/A	617.3	3.0	16/07/2020
Rugeley*	18.0	37.0	0.0	99.99	0.0*	N/A	50.0	175.0	1.3	15/04/2020
Shrewsbury	53.1	4.1	0.0	0.0	54.1	N/A	0.0	112.3	2.3	16/07/2020
Willenhall	12.5	25.5	0.0	0.0	39.9	N/A	N/A	77.9	3.6	16/07/2020

*Connections at this GSP are subject to Project Progression or Modification Application submission as the volume of Accepted Generation has exceeded Materiality Headroom and/or Fault Level Headroom. Please note Materiality Headroom and/or Fault Level Headroom figures at this GSP are subject to Project Progression or Modification Application outcome. Please follow [this link](#) to view submission timescales

** On the 3rd May 2017, WPD received notification from NGET which advised that there were significant challenges connecting additional thermal plant on the Port Ham GSP network. NGET have confirmed that the connection of further Thermal and Storage plants cannot be facilitated until completion of the wider enabling reinforcement works, currently estimated as October 2026. WPD will therefore not be in a position to energise any new thermal or storage connections to the Port Ham network until the identified NGET's works are completed. To view the latest update please click [here](#).

Category of Connection	
Part 1	Historic connections (No additions to this section)
Part 2	Connections subject to technical conditions
Part 3	Subject to interim restrictions on availability and subject to technical conditions
Part 4	Generation that can only connect on completion of works to transmission system and subject to technical conditions
Part 5	This figure will reduce as Developer Capacity is allocated or increase if projects cancel or disconnect. However, There is no guarantee or assurance that the capacity included in Part 5 will be available or that plant will be able to connect using it
Total Aggregated Developer Capacity	This figure cannot be changed or exceeded without submission of either a Modification Application, Project Progression or Statement of Works
Fault Level Headroom	The site fault level limit