

## WPD West Midlands Appendix G

GSP	Part 1 [MW]	Part 2 [MW]	Part 3 [MW]	Part 4 [MW]	Part 5 [MW]	Capacity in Project Progression/ Modification Application [MW]	Total Aggregated Developer Capacity [MW]	Fault Level Headroom [kA]	Appendix G Approval Date
<b>Bishops Wood*</b>	80.8	604.6	0.0	0.0	0.0*	12.0	691.3	2.6	13/09/2021
<b>Bushbury*</b>	52.7	115.0	0.0	0.0	0.0*	89.9	178.9	2.5	06/10/2021
<b>Bustleholm</b>	8.9	92.6	0.0	0.0	14.4	N/A	115.9	1.3	22/11/2021
<b>Cellarhead*</b>	135.5	200.7	0.0	0.0	0.0*	312.2	351.2	3.8	18/11/2021
<b>East Claydon</b>	12.3	13.1	0.0	43.0	50.0	40.0	118.31	0.0	15/10/2021
<b>Feckenham</b>	123.8	425.7	0.0	0.0	22.1	N/A	571.6	1.6	22/11/2021
<b>Iron Acton*</b>	64.5	207.3	0.0	199.1	0.0*	125.4	502.5	0.8	13/09/2021
<b>Ironbridge*</b>	57.5	192.9	0.0	0.0	0.0*	322.9	286.5	0.0*	08/11/2021
<b>Kitwell</b>	12.5	94.9	0.0	0.0	42.0	N/A	149.4	2.9	30/11/2021
<b>Lea Marston*</b>	22.1	45.1	0.0	0.0	0.0*	147.9	92.5	2.4	21/06/2021
<b>Nechells East</b>	176.0	15.0	0.0	0.0	131.7	N/A	322.7	5.8	22/11/2021
<b>Ocker Hill*</b>	4.0	63.2	0.0	0.0	0.0*	99.4	157.2	1.4	06/10/2021
<b>Oldbury</b>	38.5	60.0	0.0	0.0	10.0	N/A	108.5	1.6	22/11/2021
<b>Penn</b>	15.9	208.7	0.0	0.0	29.1	N/A	253.7	3.4	22/11/2021
<b>Port Ham*</b>	33.8	547.6	0.0	5.0	0.0*	216.8	617.3	2.5	22/07/2021
<b>Rugeley*</b>	18.0	52.0	0.0	526.5	0.0*	347.8	526.5	0.0*	08/10/2021
<b>Shrewsbury*</b>	53.1	48.1	0.0	0.0	0.0*	63.0	108.8	0.0*	08/11/2021
<b>Willenhall*</b>	12.5	25.5	0.0	0.0	0.0*	49.9	77.9	3.6	08/10/2021

\*Connections at this GSP are subject to Project Progression or Modification Application submission as the volume of Accepted Generation has exceeded Materiality Headroom and/or Fault Level Headroom. Please note Materiality Headroom and/or Fault Level Headroom figures at this GSP are subject to Project Progression or Modification Application outcome. Please follow [this link](#) to view submission timescales

<b>Category of Connection</b>	
<b>Part 1</b>	Historic connections (No additions to this section)
<b>Part 2</b>	Connections subject to technical conditions
<b>Part 3</b>	Subject to interim restrictions on availability and subject to technical conditions
<b>Part 4</b>	Generation that can only connect on completion of works to transmission system and subject to technical conditions
<b>Part 5</b>	This figure will reduce as Developer Capacity is allocated or increase if projects cancel or disconnect. However, There is no guarantee or assurance that the capacity included in Part 5 will be available or that plant will be able to connect using it
<b>Total Aggregated Developer Capacity</b>	This figure cannot be changed or exceeded without submission of either a Modification Application, Project Progression or Statement of Works
<b>Fault Level Headroom</b>	The site fault level limit